

Relining a Factory-Built Chimney for a Direct Vent Insert Can Now Be Done Safely With a Listed System

M&G DuraVent is the first manufacturer to have a UL-listed relining system for factory-built chimneys. Our co-linear direct vent relining system can be used when installing a direct vent insert into an existing factory-built chimney. When an insert is installed into an existing factory-built chimney or b vent, relining the existing chimney is critical for proper performance and safety.

Note: Plate must be larger than the current pipe or conduit. Fold brackets into existing diameter to secure the high-wind termination cap in place.

What does the UL listing cover?



All 127, 103, 103 HT chimneys or b vent
Air cooled - clearance based on diameter
Flex does not need insulation!!!

Factory-Built Reline Kit includes:

- High-Wind Termination Cap
- Two pieces of Aluminum Flex Lengths (exhaust marked red)
- 4 hose clamps

SIZE	ORDER #	STOCK #	LIST PRICE
4"x 6" Dia (2) 3'x 35' Lengths	46DVA-CL33KFB	810007970	\$326.18
4"x 6" Dia (1) 3'x 35', (1) 4'x 35' Lengths	46DVA-CL34KFB	810009663	\$326.18



DuraVent

Member of M&G Group

For current pricing and availability, please call customer service at 800-835-4429.

Information published in all M&G DuraVent bulletins is current at time of publication and is subject to change without notice.