


## PelletVent Pro PVP venting system now allows for the field application of non-combustible insulation for wall thimbles and support boxes.

DuraVent approves the field application of non-combustible insulation within the clearance to combustible distance (in wall thimbles or support boxes only) if/when desirable. Approved insulation must be listed/compliant with ASTM E136/ULC S114 as Non-Combustible, have a melting temperature above 2000°F/1100°C, be water resistant with low moisture absorption and be acceptable to the AHJ. Materials would include those made from stone (aka "rockwool" or "mineral wool" insulations). NOTE- Fiberglass insulation is NOT approved!

The latest UL approved installation instruction now available online at [www.duravent.com](http://www.duravent.com)


### Cathedral Ceiling Support Box

SIZE	ORDER #	STOCK #	A
3"	3PVP-CS	810001089	3 3/4"
4"	4PVP-CS	810001153	4 3/4"



### Wall Thimble

SIZE	ORDER #	STOCK #	A
3"	3PVP-WT	810001081	3 3/4"
4"	4PVP-WT	810001145	4 3/4"



For current pricing and availability, please call customer service at (800) 835-4429.

Information published in all M&G DuraVent bulletins is current at time of publication and is subject to change without notice.